

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-051-25034-0000  
API NUMBER 15-250340000

LEASE NAME Denis Vine

WELL NUMBER # 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4280 Ft. from (S) Section Line

670 Ft. from (E) Section Line

SEC. 26 TWP. 11 RGE. 19 (E) or (W)

COUNTY Ellis

LEASE OPERATOR Moi Oil Operations, Inc.

ADDRESS P.O. Box 33, Russell, KS 67665

PHONE(S) (785) 483-2169 OPERATORS' LICENSE NO. 67665

Date Well Completed 7-2-2000

Character of Well D+A

Plugging Commenced 8-28-00

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 8-28-00

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	244	
				5 1/2"	3667	2418

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Sanded bottom. Sand at 3554'. Bailed 5 sacks of Portland. Shot 2619', worked pipe 4'. Shot 2418', pulled to 2000'. Pumped 140 sacks. Pulled to 1475'. Pumped 50 sacks. Pulled to 1150'. Pumped 30 sacks. Pulled to 150'. Circulated Cement to surface. Pulled rest of pipe. Hole stayed full.

Name of Plugging Contractor Quality Well Service License No. 31925

Address 415 E. Main St. Sterling, Ks 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Moi Oil Operations, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Allen Bangert

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION

(Signature) Allen Bangert

(Address) P.O. Box 33, Russell, Ks 67665

SEP 12 2000  
9-12-00

SUBSCRIBED AND SWORN TO before me this 8th day of September, 2000

Verna May Hutchings  
Notary Public

My Commission Expires:  
USE ONLY ONE SIDE OF EACH FORM

VERNA MAY HUTCHINGS  
State of Kansas  
My Appt. Exp. 4-10-2004

VERNA MAY HUTCHINGS  
State of Kansas  
My Appt. Exp. 4-10-2004

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 12 2000  
9-12-00  
CONSERVATION DIVISION