


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Butler County, Sec. 27 Twp. 23 Rge. 7 (E) E (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Walker Oil Corporation
Lease Name Unruh Well No. 1
Office Address Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) D.H.
Date well completed December 18th., 1956
Application for plugging filed December 19th., 1956
Application for plugging approved December 20th., 1956
Plugging commenced December 21st., 1956
Plugging completed December 21st., 1956
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lawrence W. Matthews
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3318 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 5 sacks cement on bottom.

Mud to 135'

Set 15 sacks cement on 15' rock bridge at 120'

Mud to 15'

Set 5 sacks on 10' rock bridge.

Filled to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. J. Wixson Drilling Company
Address El Dorado, Kansas.

STATE OF KANSAS, COUNTY OF BUTLER, ss.
R. J. Wixson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Wixson
El Dorado, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December, 1956

RECEIVED
STATE CORPORATION COMMISSION Notary Public.

My commission expires August 14th., 1957.

PLUGGING
EC 27 T 23 R 7E
PAGE 126 LINE 42

JAN 2 1957
1-2-57
CONSERVATION DIVISION
Wichita, Kansas

R. J. WIXSON DRILLING COMPANY 15-015-00585-0000

COMPANY WALKER OIL CORPORATION

SEC. 27 TWP. 23 R. 7E

FARM UNRUH NO. 1

DESC. SW SW SW

COUNTY Butler KANSAS

TOTAL DEPTH 3318'

CASING RECORD:

13 3/8" 1135'

10" 1735'

8 5/8" 2375'

7" 3098'

5 1/2" 3100'

COMM. 11-11-56 COMP. 12-18-56

CONTRACTOR: R. J. WIXSON DRILLING CO.

ELEVATION 1489' PRODUCTION D&A

ISSUED: December 19th., 1956

DF

(FIGURES INDICATE BOTTOM OF FORMATION)

Cellar	8	Shale Dark	1180	Shale White	3095
Lime	20	Shale Light	1190	Shale	3097
Shale	25	Lime 1-3/4 BWP	1192-1205	Shale Light	3110
Lime	50	Shale	1220	Shale Dark	3120
Shale	65	Lime 1 1/2 BWP	1225-1235	Shale	3175
Lime	85	Shale	1245	Lime HFW 3175-3177	3220
Shale	110	Lime	1260	Lime Brown	3235
Lime	115	Shale	1265	Lime Sandy	3270
Shale	130	Lime	1275	Lime Sandy & Shale with	
Red Rock	135	Shale	1290	Green Streaks	3285
Lime	145	Lime 3 BWP	1305	Lime	3295
Shale	190	Shale	1325	Shale Green	3300
Red Rock	195	Lime	1345	Lime	3318
Lime	205	Shale	1355	Total Depth	3318
Shale	425	Lime	1390		
Lime	440	Shale	1398		
Shale	550	Lime Brkn. 1 BWP	1398-1403		
Shale Sandy 1 BWP	550-555	Shale	1445	Lansing	1785-1915
Shale	565	Lime	1490	Kansas City	2065-2230
Lime	570	Shale	1615	Mississippi	2750-3076
Shale	585	Sand Brkn. 3 BWP	1615-1630	Viola	3175-3235
Lime	590	Shale	1732	Simpson	3240-
Shale	650	Lime	1735	Arbuckle	3300-3318
Lime	655	Shale	1785		
Shale	725	Lime	1915		
Lime	745	Shale	2065		
Shale	750	Lime 1/2 BWP 2145-53	2200		
Lime	760	Shale	2205		
Shale	820	Lime Brkn.	2230		
Lime	830	Shale	2375		
Shale	835	Lime	2390		
Lime	845	Shale	2415		
Shale	865	Lime	2420		
Lime	895	Shale	2425		
Shale	900	Lime	2438		
Lime	905	Shale	2448		
Shale	1005	Lime	2455		
Lime	1010	Shale	2465		
Shale	1045	Lime	2480		
Lime	1050	Shale	2565		
Shale	1055	Lime	2575		
Lime	1060	Shale	2670		
Shale	1095	Lime	2675		
Lime	1110	Shale	2690		
Shale	1115	Shale & Shells	2715		
Lime	1120	Shale	2730		
Shale	1130	Lime	2733		
Lime	1150	Shale & Lime	2750		
Shale	1155	Lime 7 BWP 2790-2800	3076		
Lime	1170	Shale	3080		

STATE OF KANSAS }
COUNTY OF BUTLER } SS

R. J. Wixson of lawful age, being duly sworn on his oath, states that he is the Drilling Contractor or Drilling Superintendent who drilled the well described in the foregoing log, and that the above is a true and correct copy of said log.

Subscribed and sworn to before me this 19th day of December, 1956

My commission expires August 14th., 1957

PLUGGING
FILED SEC 27 T 23 R 7E
BOOK PAGE 126 LINE 42

RECEIVED
REGISTRATION COMMISSION

R. J. Wixson
Notary Public