

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 7 Twp. 26 Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines C-N/2 NW Ne

Lease Owner McKnab Drilling, Inc.

Lease Name Donner Well No. 1

Office Address 605 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 6-2 19 55

Application for plugging filed 6-2 19 55

Application for plugging approved 6-2 19 55

Plugging commenced 6-3 19 55

Plugging completed 6-3 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner

Producing formation Depth to top Bottom Total Depth of Well 4490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red bed		0	550	8-5/8	5-16-55	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Gunned up pits; got mud heavy and circulated through hole until received returns. Layed down drill pipe. Filled hole with mud to 300'. Put 1/2 sack hulls and Halliburton plug. Mixed 20 sacks cement through ten joints drill pipe. Filled hole with mud to 35'. Set 1/3 sack hulls and Halliburton plug at 35'. Put 10 sacks cement on top of plug. Tied top plug with wire line.

STATE OF KANSAS
JUN 11 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Don Gardner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

605 Union National Bank Bldg., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 19 55

Walter L. Larg

Notary Public.

My commission expires Nov. 21, 1956

PLUGGING
FILED SEC 7 T 26 R 13W
BOOK PAGE 124 LINE 32

DRILLER'S LOG
 McKnab Drilling, Inc.
 Donner #1
 C-N/2 NW NE 7-26S-13W
 Pratt County, Kansas

<u>TO</u>	<u>FROM</u>	
0	530	Red Bed, Sand & Shale
530	865	Sand, Shale & Shells
865	1635	Shale & Shells
1635	1865	Shale & Lime
1865	1990	Lime
1990	2850	Shale & Lime
2850	3110	Shale
3110	3485	Shale & Lime
3485	3595	Sand, Lime & Shale
3595	3700	Sandy Shale & Lime
3700	3837	Sand & Shale
3837	4217	Lime
4217	4265	Shale & Lime
4265	4327	Shale & Chert
4327	4375	Chert
4375	4417	Shale & Chert
4417	4430	Sand
4430	4463	Shale
4463	4490	Sand, Shale & Lime
	4490	ROTARY TOTAL DEPTH
		D & A

COMMENCED; 5-16-55
 COMPLETED: 6-3-55

CASING RECORD

Set 549' 8-5/8" surface casing with 350 sx. cem. 1% c.c. and 1% jell


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Donner #1 located in the C-N/2 NW NE of Section 7, Township 26South, Range 13 West, Pratt County, Kansas.

McKNAB DRILLING, INC.


 Don Gardner

Subscribed and sworn to before me this 8th day of June, 1955.


 Helen L. Lang
 Notary Public

My commission expires Nov. 21, 1956

PLUGGING
 TWP SEC 7 26 13W
 PAGE 24 LINE 32

RECEIVED
 STATE CORPORATION COMMISSION
 6-11-1955