

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 27 TWP. 24S RGE. 11W E/W
Location as in quarters or footage from lines:

C E/2 NW NW

Locate Well
correctly on above
Section Platt.

Lease Owner DaMac Drilling, Inc.
 Lease Name #1 Hogan Well No. _____
 Office Address Rt. 1 Box 25 Turon, Kansas 67583
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 8-15-83
 Plugging completed 8-22-83
 Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Robert Tarbutton
Producing formation _____ Depth to top _____ bottom T.D.4075'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	255'	none
				4-1/2"	4066'	1786'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3670' and ran 4 sacks cement. Shot casing @3423', 3218', 3103', 3021', 2900', 2602', 2206', 1802' and layed down a total of 41 joints (1786') of 4-1/2" casing. Plugged well with 3 hulls, 15 gel, 50 sacks 60/40 pos, 2% gel, 3% cc, 10 gel, 1 hull, plug and 100 sacks 60/40 pos, 2% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R Darrell Kelso
Box 347 Chase, Ks, 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 83



Irene Hoover
Notary Public.

My Commission expires: _____

AUG 25 1983
8-25-83
Wichita, Kansas