

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,232

LEASE NAME Frisbie "A"

WELL NUMBER 1

SPOT LOCATION W/2 SE SE

SEC. 7 TWP. 26 SRGE. 13 W (E) or (W)

COUNTY Pratt

Date Well Completed 7-12-83

Plugging Commenced 3/29/84

Plugging Completed 4/6/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F & M OIL CO., INC.

ADDRESS 422 Union Center, Wichita, Kansas 67202

PHONE # (316) 262-2636 OPERATORS LICENSE NO. 5313

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? -----

Producing formation Lansing Depth to top 3801' bottom 4104' T.D. 4495'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	407'	None
Lansing	Oil & water	3822'	3828'	4 1/2"	4152'	2481'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.  
Sanded to 3775' & ran 5 sacks cement. Shot pipe at 3630', 3500', 3300', 3100', 3000', 2700', & 2481'. Pulled 62 joints of 4 1/2". Pumped well with 3 hulls, 10 gal, 50 cement, 15 gal, 1 hull, released plug, & 125 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelson Casing Pulling License No. 6050  
Address Box 347, Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 10th day of April, 1984



Irene Hoover  
Notary Public

My Commission expires:

RECEIVED  
STATE CORPORATION COMMISSION  
APR 12 1984  
4-12-84  
CONSERVATION DIVISION  
Wichita, Kansas