

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pratt County, Sec. 6 Twp. 26S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines NE Corner Lot 5
Lease Owner Amarex, Volunteer & Sage
Lease Name Henderson Well No. 1
Office Address 500 Bitting Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 23, 1969
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced July 23, 1969
Plugging completed July 23, 1969
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Ralph Warren of Pratt)

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4525 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	330'	8-5/8"	330'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from Total Depth to 450 Feet;
Plug and 50 sax cement; Mud to
260 Feet; Plug and 25 sax cement;
Mud to 40 Feet; 1/2 sax Hulls, plug
bridged w/Kelly and 10 sax cement
to Base of Cellar; 2 sax cement
in Rat Hole. Job Completed at
8:30 A.M. by Allied.

RECEIVED
7-28-69
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Allied Cementing Co.
Address Box 207, Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of July 19 69

My commission expires November 26, 1970.
Louise K. Whitted - Notary Public.



DRILLERS LOG

HENDERSON NO. 1

CASING RECORD: OPERATOR: Sage Drilling Co., DESCRIPTION:
8-5/8" @ 330' Volunteer & Amarex
w/225 sax cement CONTRACTOR: Sage Drilling Co. NE Corner Lot 5
COMMENCED: July 15, 1969 Sec. 6-26S-13W
Pratt County, Kansas
TOTAL DEPTH: COMPLETED: July 23, 1969 ELEVATION: 1971KB
4525'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Top Soil & Sand	0	52	
Shale	52	72	
Sand	72	205	
Shale	205	375	
Shale, Shells & Red Bed	375	877	
Anhydrite	877	895	
Shale, Shells & Salt	895	1285	
Shale	1285	1805	
Lime & Shale	1805	2800	
Shale & Lime	2800	3030	
Lime & Shale	3030	3654	
Shale & Lime	3654	3671	
Lime & Shale	3671	3825	
Lime	3825	4107	
Shale, Chert & Lime	4107	4195	
Lime, Chert & Shale	4195	4424	
Chert, Simpson Shale & Sand	4424	4485	
Cherty Shale & Sand	4485	4497	
Arbuckle	4497	4525	D&A

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that the above is a true and correct copy of the log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 25th day of July, 1969.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.