


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 11 Twp. 26S Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW SW NW  
Lease Owner Rains & Williamson Oil Co.  
Lease Name Griffith Well No. 1  
Office Address 1425 Wichita Plaza Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-31 19 63  
Application for plugging filed 12-31 19 63  
Application for plugging approved 12-31 19 63  
Plugging commenced 12-31 19 63  
Plugging completed 12-31 19 63  
Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation None Depth to top Bottom Total Depth of Well 4050 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	416'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 400 feet. Cement through drill pipe with 30 sacks cement. Fill hole with rotary mud to 40 feet of base of cellar. Set plug and hulls and cap with 12 sacks cement. Plugging completed at 8:30 p.m. Plugging permission from Archie Elving at Pratt, Kansas.

RECEIVED  
STATE CORPORATION COMMISSION  
1-7-64  
JAN 7 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 1425 Wichita Plaza Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Wilson Rains

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
1425 Wichita Plaza Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 64

My commission expires August 14, 1966

Sandra Ames  
Sandra Ames Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co.  
and George Grenyo, et al  
No. 1 Griffith  
C NW SW NW Sec. 11-26S-13W  
Pottawatomie County, Kansas

CONTRACTOR: Rains & Williamson  
Oil Co.  
COMM: 12-22-63  
COMP: 12-31-63

Remarks: Set 8-5/8" surface casing at 415' with 280 sacks cement.

Formations:

Sand	60'
Shale & Sand	360'
Sand	370'
Shale	416'
Red Bed	645'
Shale & Red Bed	756'
Lime	778'
Shale & Shells	1710'
Shale & Lime	1960'
Lime	2110'
Lime & Shale	2460'
Shale & Lime Streaks	2660'
Shale & Lime	3000'
Lime & Shale	3484'
Lime	4050'
Rotary Total Depth (D&A)	4050'

RECEIVED  
STATE CORPORATION COMMISSION

JAN 15 1964

CONSERVATION DIVISION  
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
Wilson Rains  
Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 6th day of January, 1964.

My Commission Expires: August 14, 1966

*Sandra Ames*  
Sandra Ames, Notary Public