

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED
DEC 04 2001
11-4-01
KCC WICHITA
TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

15-151-21,473-00-00-01
API NUMBER
LEASE NAME Keller "E" (G)
WELL NUMBER 6-F
1320 ft. from S Section Line
2050 ft. from E Section Line
SEC. 11 TWP. 26 RGE. 13 (E) or (W)
COUNTY Pratt

LEASE OPERATOR Younger Energy Company
ADDRESS 453 S. Webb Road, Ste 100, Wichita, KS 67207
PHONE # (316) 681-2542 OPERATORS LICENSE NO. 30705

Character of well oil
(Oil, Gas, D&A, SWD, input, Water Supply Well)

Date Well Completed
Plugging Commenced 11/2/01
Plugging Completed 11/5/01

The plugging proposal was approved on 11/2/01 (date)
by Steve Durant (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation Depth to Top Bottom T.D. 4375
Show depth and thickness of all water, oil and gas formations
OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	324	none
				4 1/2	4099	2618

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set

Sand at 3700, baled 4 sacks cement. Shot pipe at 2827, 2618. Pulled 45 jts. to 800'. Pumped 10 sacks gel, 50 sacks cement. Pulled 12 jts. to 360 and pumped 50 sacks cement. Pulled 8 jts. to 40' and pumped 10 sacks cement.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Younger Energy Company

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

GARY P. YOUNGER (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.


(Signature) Gary P. Younger

(Address) 453 S. Webb, Suite 100, Wichita, KS

SUBSCRIBED AND SWORN TO before me 3RD day of DECEMBER, 2001

Diane Rebstock
Notary Public

My commission Expires: MARCH 29, 2002



OR