

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record

API NUMBER

15-151-22192-0000

K.A.R. -82-3-117

LEASE NAME

Wahrman

RECEIVED
1-17-03

WELL NUMBER

1-32

JAN 17 2003

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

990 Ft. from North Line of Section

KCC WICHITA 990 Ft. from East Line of Section

LEASE OPERATOR Dunne Equities Operating, Inc. SPOT LOCATION SW Ne Ne
ADDRESS 8100 E 22nd St. No., Bldg. 1100 Section 32 Township 29s Range 15w
CITY, STATE, ZIP Wichita, Kansas 67226-2311 County Pratt
PHONE # 316-684-6508 Date Well Completed 01/13/03
Character of Well Dry and Abandoned Date Plugging Commenced 01/13/03
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 01/13/03

The plugging proposal was approved on January 10, 2003 (date)
by Richard Lacey (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes

Producing Formation(s) D&A Depth to Top Bottom T.D. 4950

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180			
Redbeds	Shale	180	290	8-5/8"	272.77'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well using 185sx of 60/40 Poz, 6% Gel in the following manner; Heavy mud in hole.

Bottom plug at 4890' - 50sx, 2nd plug at 950-50sx, 3rd plug at 310' - 50sx, top plug at 40'-

10sx cemented to surface. Rathole 15sx, mousehole 10sx. Plug down at 10:15 pm

on 01/13/03. Allied Cementing ticket #5731. Reported plugging to KCC 01/15/03.

Name of Plugging Contractor Sterling Drilling Company

Licence No. 5142

Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dunne Equities Operating, Inc. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 16th day of January, 2003



[Signature]
(Notary Public)

My Commission Expires: _____

OR

RECEIVED
JAN 17 2003
KCC WICHITA

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Wahrman 1-32

LOCATION: SW Ne Ne Section 32 T 29s R 15w
API: 15-151-22192-0000 Pratt County, Kansas

OWNER: Dunne Equities Operating, Inc.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 01/02/03
COMPLETED: 01/13/03

TOTAL DEPTH: **DRILLER** 4950 FEET
LOGGER 4946 FEET

Ground Elevation: 1997
KB Elevation: 2006

LOG

0 -	4 FEET	Top Sand
4 -	12 FEET	Clay
12 -	18 FEET	Sand and Gravel
18 -	40 FEET	Clay
40 -	62 FEET	Sand and Gravel
62 -	80 FEET	Clay
80 -	210 FEET	Shales and Clay
210 -	834 FEET	Redbeds
834 -	847 FEET	Anhydrite
847 -	2205 FEET	Shales and Salt
2205 -	4850 FEET	Limestone/Shales
4850 -	4950 FEET	Arbuckle

CASING RECORDS

Surface Casing:

Spud @ 5:00 pm on 01/02/03. Drilled 12-1/4" hole to 290'. Ran 6 joints of new 23# 8-5/8" surface casing tally 272.77' set at 283.77' KB. Cemented with 175 sx 60/40 Poz, 3% CC,, 1/4 lb/sx celloflake. Plug down at 10:15 pm on 01/02/03. Cement did circulate. Acid Services ticket #5727. Welded straps on bottom 3 joints, welded collars on remaining 3 joints.

Plugging Record:

Plugged well using 185sx of 60/40 Poz, 6% Gel in the following manner; Heavy mud in hole. Bottom plug at 4890' - 50sx, 2nd plug at 950-50sx, 3rd plug at 310' - 50sx, top plug at 40' - 10sx cemented to surface. Rathole 15sx, mousehole 10sx. Plug down at 10:15 pm on 01/13/03. Allied Cementing ticket #5731. Reported plugging to KCC 01/15/03.

DEVIATION SURVEYS

1 degree(s) at	290	feet
3/4 degree(s) at	4770	feet
1-3/4 degree(s) at	4950	feet