

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

## WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 33 TWP. 29S RGE. 15W E/W  
Location as in quarters or footage from lines:

C of SE SW


Lease Owner Imperial Oil Company  
Lease Name Gilliam 1-33 Well No. \_\_\_\_\_  
Office Address 720 Fourth Financial Center Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 1-2-82  
Plugging completed 1-8-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4865

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	406'	none
				4-1/2"	4864'	3215'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 4650' and ran 4 sacks cement. Shot pipe @3990', 3830', 3615', 3420' and 3210'. Pulled a total of 78 joints of pipe. Plugged well with 15 sacks gel, 6 sacks hulls, 20 sacks gel, released plug, and displaced with 150 sacks common cement, 2% gel, 3% cc. Plugging Completed

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 82

My Commission expires: \_\_\_\_\_



Irene Hoover  
Notary Public.

FILED 14 1082  
1-14-82  
CONSERVATION DIVISION  
Wichita, Kansas

# DRILLERS LOG

OPERATOR: Imperial Oil Co. 720 4th Financial Center Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Gillam Well No. #1-33

Sec. 33 T. 29S R. 15W Spot C SE SW

County Pratt State Kansas Elevation \_\_\_\_\_

## Casing Record:

Surface: 8 5/8 @ 415' with \_\_\_\_\_ Sxs.

Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ Sxs.

Type Well: Oil Total Depth 4865'

Drilling Commenced: 10-19-81 Drilling Completed 10-31-81

Formation	From	To	Tops
-----------	------	----	------

Cellar	0	7	
Sand	7	1723	
Lime & Shale	1723	3997	
Lime	3997	4865	

RECEIVED  
STATE CORPORATION COMMISSION

FEB - 8 1982

CONSERVATION DIVISION  
Wichita, Kansas

## COMPLETION RECORD

Liner Record: Size \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_

Cementing Record: \_\_\_\_\_ Sacks \_\_\_\_\_

## Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: \_\_\_\_\_

Electric Log

Type and Depths Covered
