

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

21612-00-00  
API NUMBER 15-151-21621

LEASE NAME Howell

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div. C-NE-SE  
office within 30 days.

C-NE-SE Ft. from S Section Line  
           Ft. from E Section Line

LEASE OPERATOR McGuinness Oil Co.

SEC. 36 TWP. 29S RGE. 15 KEXXX(W)

ADDRESS 1026 Union Center, Wichita, KS 67202

COUNTY Pratt

PHONE# (316) 267-6065 OPERATORS LICENSE NO.           

Date Well Completed 5/19/85

Character of Well D & A

Plugging Commenced 6/18/85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/8/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed?            if not, is well log attached? yes

Producing Formation            Depth to Top            Bottom            T.D. 4640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	346	None
				4 1/2	4639	2636

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Plug back at 4250, sand from 4250 to 4150, 4sx cement with dump bailer 4150 to 4120, ripped at 2900, 2850 and 2636, 3sx hulls, 10sx jell, 50sx cement, 10sx jell, 1 plug, 125sx cement 60-40 POZ, 6% Jell

Jack Luthie and E. Morgenstern on location

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp. License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Elmo Morgenstern

(Address)           

CAREN J. McCULLOUGH  
NOTARY PUBLIC  
STATE OF KANSAS

My Appt. Exp. June 29, 1987

SUBSCRIBED AND SWORN TO before me this 17 day of July, 19 85

Caren J. McCullough  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

Commission Expires: June 29, 1987  
JUL 22 1985  
7-22-85  
CONSERVATION DIVISION  
Wichita, Kansas