


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plot

Pratt County, Sec. 4 Twp. 26 Rge. 13 (E) (W)
Location as "NE/CNWSW" or footage from lines SW SW SE
Lease Owner Halliburton Oil Producing Co.
Lease Name Belden Unit #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 1-13 1973
Application for plugging filed 11-5 1975
Application for plugging approved 11-7 1975
Plugging commenced 11/25/75 19
Plugging completed 12/3/75 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 11-5 1975
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Lansing Depth to top 3750 Bottom 4040 Total Depth of Well 4040
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	331	none
				4 1/2"	3920	3111'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, to 3866', ran sand to 3750' and ran 3 sacks cement.
Loaded hole with water, shot pipe at 3278', 3192', 3108', pulled 95 joints. Allied pumped 2 sacks hulls, 10 sacks mud and 100 sacks cement.
PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1975

My commission expires
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

Rec'd
12-18-75
12-18-75

DRILLERS LOG

BELDEN UNIT NO. 1

CASING RECORD: 8-5/8" @ 331'
w/225 sax cement

OPERATOR: Halliburton Oil Producing Co.

CONTRACTOR: Sage Drilling Co., Inc.

COMMENCED: December 22, 1972

COMPLETED: January 7, 1973

DESCRIPTION: Ap SW NW SE
Sec. 4-26S-13W
Pratt County,
Kansas.

TOTAL DEPTH:
4040'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	335	
Shale, Sand and Shells	335	825	
Anhydrite	825	850	
Shale	850	1990	
Lime & Shale	1990	2155	
Shale	2155	2260	
Shale & Lime	2260	2681	
Shale	2681	2790	
Lime & Shale	2790	3090	
Lime	3090	4040	4 1/2" set @ 3920' w/125 sax cement

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 11th day of January, 1973.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.

RECEIVED
STATE COMMISSIONER OF GEOL. & MIN. SURV.
TOPEKA, KANSAS

NOV 7 1973

COMMISSION DIVISION
TOPEKA, KANSAS