

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Reno County. Sec. 5 Twp. 24 Rge. 10 (E) 10 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW 1/4 NW 1/4 NE 1/4

Lease Owner Simpson Oil Company

Lease Name Paine Well No. 1

Office Address 713 First Nat'l. Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) DRY

Date, well completed 12-7 193 41

Application for plugging filed 12-3 193 41

Application for plugging approved 12-3 193 41

Plugging Commenced 12-3 193 41

Plugging Completed 12-7 193 41

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola	Water	0	185	12 1/2"	185	
		0	3850	7"	3850	3201

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from 3850' to 3825'. Cement from 3825' to 3800'. Mud from 3800' to 185'.  
Bridge at 185'. Cement from 185' to 165'. Mud from 165' to 14'. Bridge set at 14'.  
Cement from 14' to bottom of cellar. Weld steel cap over surface pipe. Cement was put in hole with dump bailer.

PLUGGING  
FILE 5-24-100  
BOOK PAGE 16 LINE 8

REC'D  
12-15-41

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Simpson Oil Company

Address 713 First Nat'l. Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Sam Payne, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sam Payne, Jr.

Wichita, Kansas, 713 First Nat'l. Bldg.

(Address)

SUBSCRIBED AND SWORN to before me this 15th day of December, 1941

March 30, 1944

Notary Public

PAINE WELL NO. 1


SW 1/4 NW 1/4 NE 1/4 5-24-10W, Reno County, Kansas.  
 Owner: Simpson Oil Company et al.  
 Casing: 12 1/2" @ 185'  
           7" @ 3850'

Commenced: 10-4-41

Elevation: 1790  
 Total Depth: 3850'  
 DRY

Log

Sand	15
Clay	23
Sand	165
Red rock	185
Red bed	475
Anhydrite	495
Blue shale & shale	860
Shale & shells	1100
Salt & shale	1274
Shale & shells	1450
Broken lime	2219
Lime	2310
Broken lime	2644
Lime & shale	2717
Broken lime & shale	2785
Lime & shale	2884
Lime	3067
Broken lime	3173
Lime	3211
Soft lime	3215
Shale blue & brown	3304
Shale	3308
Broken lime	3329
Broken lime & shale	3365
Lime K. C.	3396
Lime	3572
Lime & shale	3628
Shale	3667
Chert	3717
Shale	3819
Lime	3850



RECORDS  
 FILE 5-24-10W  
 BOO 16-NE-8