


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

19
WELL PLUGGING RECORD

Reno County, Sec. 5 Twp. 24 Rge. 10 (E) (W) ^x
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Leben Drilling Inc.
Lease Name Barr Well No. #1
Office Address Box 486, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed 9-25-61 19____
Application for plugging approved _____ 19____
Plugging commenced 9-26-61 19____
Plugging completed 10-4-61 19____
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3807 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole back to 3680' with 5 sacks cement with dump bailer
Pumped plug down to 3000'
Mudded hole to 250', set 10' rock bridge with 5 sacks cement.
Mixed and ran 15 sacks cement. Mudded hole to 35', set 10' rock bridge
with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1961
10-6-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5 day of October, 19 61

My commission expires 24 October 1964
Sidney D. Miller
Notary Public.

LEBEN DRILLING COMPANY

#1 BAAR
SW SW NW Section 5-24S-10W
Reno County, Kansas

Contractor: Leben Drilling, Inc.
Commenced: August 17, 1961
Completed: August 29, 1961

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Sand and Red Bed	255
Shale and Shells and Red Bed	665
Shale and Shells	1525
Lime and Shale	2780
Shaley Lime	2911
Lime and Shale	3333
Lime and Cherty	3395
Lime and Shale	3476
Lime	3585
Lime and Shale	3630
Lime and Chert	3677
Lime and Shale	3708

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I hereby certify that the above is true and correct to the best of my knowledge.

Byron Johnson
Byron Johnson
LEBEN DRILLING, INC.

Subscribed and sworn to before me this 25th day of September, 1961

Ulanda Nichols
Ulanda Nichols

My Commission Expires:
April 1, 1963



10-17-61
RECEIVED
STATE CORPORATION COMMISSION
OCT-17-1961
CONSERVATION DIVISION
Wichita, Kansas