


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Russell County, Sec. 6 Twp. 14S Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NE NW

Lease Owner R. P. Nixon Operations
Lease Name Hazelhorst Well No. #1
Office Address 207 W. 12th Street, Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plat

Date Well completed 10-5-78 19
Application for plugging filed 10-5-78 19
Application for plugging approved 10-5-78 19
Plugging commenced 10-5-78 19
Plugging completed 10-5-78 19
Reason for abandonment of well or producing formation Commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin, Great Bend, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3345'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 500' w/50 sx.
Plug @ 210' w/25 sx.
Plug @ 40' w/10 sx.
Rat Hole 2 sx.

RECEIVED
STATE CORPORATION COMMISSION
10 19 78
OCT 19 1978


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Buffalo Drilling Company, Inc. CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Wilson Rains of Buffalo Drilling Company, Inc. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of October, 1978



Juanita M. Green
Notary Public.

My commission expires 10-4-79

DRILLER'S LOG

COMPANY: R. P. Nixon Operations

SEC. 6 T. 14S R. 15W

WELL NAME: Hazelhorst #1

LOC. SE NE NW

COUNTY: Russell

RIG NO. #7

TOTAL DEPTH 3345'

ELEVATION

COMMENCED: 9-28-78

COMPLETED: 10-5-78

CONTRACTOR: Buffalo Drilling Company, Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 216' w/150 sx. 60/40 poz., 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Shale	340
Shale & Redbed	954
Shale & Shells	1315
Shale & Sand	1705
Shale & Lime	2262
Lime	2664
Lime & Shale	2812
Lime	3345
<u>ROTARY TOTAL DEPTH</u>	<u>3345</u>

10-19-78
 RECEIVED
 STATE CORPORATION COMMISSION
 OCT 19 1978
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF Kansas)
 COUNTY OF Sedgwick)

SS:

I, Wilson Rains of Buffalo Drilling Company, Inc.
 upon oath state that the above and foregoing is a true and correct copy of the log of the
Hazelhorst #1 well.

Wilson Rains
 Wilson Rains

Subscribed and sworn to before me this 10 day of October, 1978.

My Appointment Expires:
10-4-79

Juanita M. Green
 Juanita M. Green

