


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 15 Twp. 24 Rge. 4 (E) (W)
Location as "NE/CNW/SW" or footage from lines 510 EWL 660 SWL NW/4
Lease Owner Home Stake Production Company
Lease Name Pitts O-13 Well No.
Office Address Burrton, Kansas 67020
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8/5/68 19
Plugging completed 8/9/68 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation Depth to top Bottom Total Depth of Well 3378 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	328	none
				5 1/2	3345	1436

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3325' and dumped 5 sacks of cement.
Rigged up on 5 1/2" pipe parted down hole, pulled out 12 joints.
Ran die nipple, got hold of pipe, loaded hole, shot pipe at 2018', 1925' and worked pipe. Shot pipe at 1837', 1742', 1650', 1547', 1431', worked pipe loose and pulled 46 joints total.
Set 10' rock bridge at 310' and dumped 35 sacks of cement.
Mudded to 35' and dumped 15 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1968 8-16-68
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 12th day of August

19 68

My commission expires February 15, 1971

Notary Public.

HOME-STAKE PRODUCTION COMPANY
PHILTOWER BUILDING
TULSA, OKLAHOMA

WELL RECORD FOR
WELLS IN KANSAS

Farm Name: PITTS Well Number: 0-13
In the: Haven Waterflood Project Character of Well: 011
Located in: Reno County, Kansas Section 15 Twn. 24S Range 4 West
Well Spot: NW/4

510' East of West line and 660' South of North line.

Ground Elevation: 1468' K. B. Elevation: 1473'
Drilling Started: August 3, 1963 NOTE: All measurements are from the K. B.
Drilling Completed: August 8, 1963 Well Completed: June, 1964
DATE OF FIRST PRODUCTION: June 30, 1964 DATE OF FIRST INJECTION: - - -
Casing Record: Set at 328' - 10-3/4", 40#, used, surface casing.
Set at 3345' - 5-1/2", 14#, used casing.

Cementing Record: 300 sacks common cement w/2% Gel and 2% CC added for surf. csg.
125 sacks common cement for the long string.
Cement was circulated.

Fracture or Shot Record: None
EFFECTIVE PAY ZONE: MISSISSIPPI (Tripolitic) CHAT

PERFORATED: None - open hole. No. of Shots _____
No. of Shots _____
No. of Shots _____
No. of Shots _____
No. of Shots _____
Total number of holes _____

FORMATION RECORD

Rotary drilled: Surface to 3351'
Cable tools: 3351' to 3378'

	Top	Bottom
Sand and shale	-0-	331
Shale	331	565
Lime and shale	565	1175
Shale and lime streaks	1175	1735
Lime and shale	1735	2337
Shale and lime streaks	2337	2508
Sand and shaley sand	2508	2543
Shale	2543	2565
Lime and shale	2565	2602
Lime-Lansing-Kansas City	2602	3187
Shale	3187	3303
Mississippi Lime	3303	3345
Mississippi (Trip.) Chat	3345	3378
Total depth		3378'

*Sub Sec 2-
(1872-1905)*

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1968
CONSERVATION DIVISION
Wichita, Kansas

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct & complete according to our records and to the best of my belief and knowledge.

David C. Jones Vice Pres. Exploration

Name and title of representative of company

Subscribed and sworn to before me this 2 day of September, 1964

My Commission expires January 29, 1967

Leis M. Nicklaus
Notary Public