


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission,
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Reno County, Sec. 15 Twp. 24 Rge. 4 (E) (W)
Location as "NE/CNW4SW4" or footage from lines 80 SNL 1270 EWL N8/4
Lease Owner Homa Stake Production Company
Lease Name Pitts Well No. W-42-61-29
Office Address Burrton, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6/26/68 19
Plugging completed 6/27/68 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman

Producing formation Depth to top Bottom Total Depth of Well 3376 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	317'	none
				4 1/2"	3359'	2433'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3376', ran sand to 3340' and dumped 3 sacks of cement. Loaded hole, shot pipe at 2444', worked pipe loose and pulled 76 joints. Set 10' rock bridge from 310 to 300' and dumped 30 sacks of cement. Mudded hole to 40', set 10' rock bridge and dumped 15 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
JUL 2 1968
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT

(employee or operator) of the above-described well, being first duly sworn, on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

Subscribed and sworn to before me this 28

day of June

19 68

My commission expires February 15, 1971

Notary Public.

HOME-STAKE PRODUCTION COMPANY
PHELLOWER BUILDING
TULSA, OKLAHOMA

WELL RECORD FOR
WELLS IN KANSAS

Farm Name: PITTS Well Number: W-29

In the: Haven Waterflood Project Character of Well: WATER INPUT

Located in: Reno County, Kansas Section 15 Twn. 24S Range 4 West

Well Spot: NW/4

80' South of North line, and 1270' East of West line.

Ground Elevation: 1466' K. B. Elevation: 1471'

Drilling Started: November 26, 1963 NOTE: All measurements are from the K. B.

Drilling Completed: December 2, 1963 Well Completed: March, 1964

DATE OF FIRST PRODUCTION: - - DATE OF FIRST INJECTION: March, 1964

Casing Record: Set at 317' - 10-3/4", 40#, Used, surface casing.

Set at 3356' - 4-1/2", 9.5#, J-55, New casing.

Cementing Record: 300 sacks cement with 2% Gel & 2% CC added for surface casing.

150 sacks common cement for the long string.

Cement was circulated.

Fracture or Shot Record: None

EFFECTIVE PAY ZONE: MISSISSIPPI (Tripolitic) CHAT

PERFORATED: None - open hole. No. of Shots

 No. of Shots

 No. of Shots

 No. of Shots

 No. of Shots

Total number of holes

FORMATION RECORD

Rotary drilled: Surface to 3376'

Cable tools:

	Top	Bottom	Top	Bottom
Surface soil	-0-	510		
Lime	510	1050		
Lime and shale	1050	1225		
Shale and lime	1225	1665		
Shale	1665	2020		
Shale and lime	2020	2504		
Lime	2504	2538		
Shale	2538	2564		
Lime	2564	2570		
Shale	2570	2601		
Top Lansing-Kansas City	2601			
Lime beds with shale breaks	2601	3198		
Shale and shaley lime	3198	3315		
Mississippi lime	3315	3355		
Mississippi (Tripolitic) Chat	3355	3376		
Total Depth	3376'			

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1968
CONSERVATION DIVISION
Wichita, Kansas

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct & complete according to our records and to the best of my belief and knowledge.

David C. Davis Vice Pres. Exploration
Name and title of representative of company

Subscribed and sworn to before me this 8 day of May, 1964

My Commission expires January 29, 1967

Louis M. Nicklass
Notary Public