


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 30 Twp. 24S Rge. 11W(E) (W)
Location as "NE/CNW/SW" or footage from lines C SW NW NE
Lease Owner Cooperative Refinery Association
Lease Name Davis "K" Well No. 1
Office Address Drawer C - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed September 15 1961
Application for plugging filed October 6 1961
Application for plugging approved October 9 1961
Plugging commenced October 12 1961
Plugging completed October 19 1961
Reason for abandonment of well or producing formation Not economical

If a producing well is abandoned, date of last production September 29 1961
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lackamp
Producing formation Viola Depth to top 3902 Bottom 3904 Total Depth of Well 3907 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3902'	3,057'
				8 5/8"	304'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 10-12-61: Plugging complete 10-19-61

Measured in to T.D. plug at 3907'. Sanded back from 3907' to 3900', dumped 5 sacks cement. Worked and shot casing. Loaded hole with water. Spotted oil. Worked and shot 5 1/2" casing free at 3,057'. Built rack and slide. Pulled and laid down casing. Bailed down hole. Mudded up to 300' and set 10' rock bridge. Dumped 20 sacks cement. Mudded up to 40' and set 10' rock bridge. Capped the well with 10 sacks cement. Complete

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1961
11-7-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
Jim Robinson
Drawer C - Great Bend, Kansas

SUBSCRIBED AND SWORN to before me this 31 day of October, 1961

My commission expires April 4, 1964
Barbara J. Marquardt
Barbara J. Marquardt Notary Public.

Davis #1

Elevation: 1843 K.B.
Casing: 8 5/8" @ 304' w/ 200 sz.

Loc: C SW NW NE

Sec: 30-21S-11W

Stafford County, Kansas

Operator: Cooperative Refinery Assn.

Contractor: Company Rig #5

5 1/2" @ 3902 K.B. w/ 75 sz.

Com: 9-4-57 Corp: 9-15-57
R.T.D. 3904'

<u>From</u>	<u>To</u>	<u>Formation</u>
0	100	Clay and sand
100	304	Clay, shale, sand
304	550	Shale, redbed
550	870	Redbed, shale, shells
870	1400	Shale, shells, sand
1400	2265	Lime and shale
2265	2390	Shale
2390	2585	Shale and lime
2585	2755	Shale, lime, shells
2755	3705	Shale and lime
3705	3735	Lime
3735	3875	Lime and shale
3875	3904	Lime, shale, chert
3904		R.T.D.

11-1-61

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Davis #1 well, located C SW NW NE of Section 30-21S-11W, Stafford County, Kansas.

Morris D. Sullivan

Subscribed and sworn to before me this 18 day of September 1957.

Yvonne Adams

My commission expires: September 24, 1960.