

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 24 Twp. 24S Rge. 11W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Sunray DX Oil Company
Lease Name McComb Well No. 1
Office Address 321 West Douglas, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 19 1938
Application for plugging filed April 21 1964
Application for plugging approved April 22 1964
Plugging commenced April 22 1964
Plugging completed April 28 1964
Reason for abandonment of well or producing formation Reached economic limit

NORTH

Section Plat grid with 'X' in the top-left cell.

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production January 19 64
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Box 248, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3808 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Includes data for 10-3/4" and 7" casing sizes.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with sand to 3785'. Run 6 sacks cement from 3785' to 3755'. Fill hole with mud to 250' and rock to 240'. Run 30 sacks cement from 240' to 190'. Fill with mud to 40' and rock to 30'. Run 15 sacks cement 30' to cellar. Surface casing cemented.

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1964
5-19-64

Log Attached

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service
Address Route #3, Hutchinson, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
N. A. Gough (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

321 W. Douglas, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1964

My commission expires July 13, 1967

Notary Public.

