

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,796-0000

LEASE NAME Paulsen

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
2310 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR Honey Oil Co., Inc.

SEC. 24 TWP. 24 RGE. 11 (E) or (W)

ADDRESS 401 East Douglas - Suite 505 Wichita, KS 67202

COUNTY Stafford

PHONE#(316) 265-7300 OPERATORS LICENSE NO. 30080

Date Well Completed 08-25-91

Character of Well D&A

Plugging Commenced 08-25-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 08-25-91

The plugging proposal was approved on 08-23-91 (date)

by Richard Lacey (KCC District Agent's Name).

to be filed
Is ACO-1 filed? by operator If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3898'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
						<u>8-29-91</u>
						<u>AUG 29 1991</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom plug: @ 600' w/50 sacks cement thru drill pipe

Next Plug: @ 270' w/50 " " " " " 15 sacks in rat Hole

Top Plug: @ 40' w/10 " " " " " 10 sacks in Mouse hole

5 sacks in water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.


John Armbruster (Employee of Operator) or ~~Operator~~ of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) John J. Armbruster

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 28th day of August, 19 91

My Commission Expires:



Notary Public

DRILLER'S WELL LOG

DATE COMMENCED: August 19, 1991
DATE COMPLETED: August 25, 1991

Honey Oil Co., Inc.
PAULSEN #1
C N/2 NE SW
Sec. 24, T24S, R11W
Stafford County, Ks.

0 - 129' Surface Soil, Sand, Clay
129 - 244' Sand, Shale
244 - 1543' Clay, Shale, Lime
1543 - 3591' Lime & Shale
3591 - 3711' Lime
3711 - 3785' Chert & Lime
3785 - 3898' Lime & Shale
3898' RTD

elevation; 1793 K.B.

Surface Pipe: Set used
8-5/8", 28# pipe @243'
w/140 sacks 60/40 pozmix
2% gel 3% cc.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss


AUG 29 1991

CORRELATION DIVISION
Wichita, Kansas

John Armbruster of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

John J. Armbruster

Subscribed and sworn to before me this 28th day of August 1991.



Paula Ann Laudick
Notary Public