

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 11 Twp. 24 Rge. (E) 12 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW-NE-NW
Lease Owner Herman Geo. Kaiser Oil Producer
Lease Name Hildebrand Well No. 4
Office Address 909 Palace Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed May 24th 19.50
Application for plugging filed March 24th 19.55
Application for plugging approved March 25th 19.55
Plugging commenced May 20th 19.55
Plugging completed May 26th 19.55
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production March 15th 19.55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation Viola Depth to top 3810' Bottom 3812' Total Depth of Well 3812' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	200'	none
				5-1/2"	3811'	1866'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3812' to 3800' Sand bridge
3800' to 3770' 5 sacks cement
3770' to 225' mudded
225' to 210' Rockbridgement
210' to 150' 20 sacks cement
150' to 30' mudded
30' to cellar 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 - 1955
6-4-55
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Herman Geo. Kaiser Oil Producer
Address 909 Palace Bldg., Tulsa, Okla.

STATE OF _____, COUNTY OF _____, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HERMAN GEO. KAISER

(Signature) OIL PRODUCER

BY [Signature] (Address)

SUBSCRIBED AND SWORN to before me this 4th day of June, 19.55
Seward S. Greider

Notary Public.

My commission expires 1-31-57

PLUGGING
FILE SEC 11 T 24 R 12W
BOOK PAGE 106 LINE 45

Company: M. B. Anner
 Contractor: Judy Drilling Company, Inc.
 Drilling commenced: 5/11/50
 Drilling completed: 5/25/50
 Elevations: 1842 B. F.
 1824 B. B.
 1850 Gr.

Form: Hildbrand - well #1
 Location: (S 1/4 Sec 11, T 24 N, R 12 W)
 Stafford County, Kansas
 Casing records: 8-5/8" O.D. 120' cemented
 w/ 600 lbs
 5-0/10" O.D. 110' cemented
 w/ 200 lbs

(Distances below indicate to base)

Clay	55
Sand	150
Red soil	200
Red soil, shale & cholla	607
Anthracite	620
Shale	650
Shale & cholla	700
Lime	7100
Lime & shale	2500
Lime	2500
Lime, broken	2507
Shale & lime	2550
Shale	2580
Lime & shale	2585
Lime	2585
Lime & shale	2610
Lime	2610
Lime & shale	2655
Lime	2655
Shale	2655
Shale, lime & cholla	2680
Shale	2680
Total depth	2680

CONTRACTOR'S SIGNATURE (M. B. Anner)

DATE OF SIGNATURE 5/25/50

I hereby certify that this is a true and correct copy of the above described well as shown by the drilling reports.

OFFICIAL SIGNATURE (M. B. Anner, P.E.)

PLUGGING
 FILE SEC 11 T 24 R 12 W
 BOOK PAGE 106 LINE 4/5