


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Reno County, Sec. 25 Twp. 23 Rge. 5 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE  
Lease Owner Pam-Kar Drilling Co., Inc.  
Lease Name Coberly Well No. 1  
Office Address 333 1st Nat'l. Bank Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 2 19 54  
Application for plugging filed " " 19 " "  
Application for plugging approved " " 19 " "  
Plugging commenced " " 19 " "  
Plugging completed " " 19 " "  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3890 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13"	207'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud pushed in hole to 204' set plug. Poured 1/2 sack hulls and then 1/2 bbl rock. Mixed and poured 30 sks cement filling hole to 18' below bottom of cellar. Pushed plugg to 18'. Poured 1/2 sk of hulls and 1/2 bbl rocks. Poured 8 sks cement filling hole to top. All plugs were secured with 2 strands of HOWCO steel line.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1954  
7-15-54  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pam-Kar Drilling Company, Inc.  
Address 333 1st National Bank Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.  
I, Ralph B. McLaughlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B. McLaughlin

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 54

My commission expires Sept. 4, 1957

Notary Public.

PLUGGING  
FILE SEC 25 T 23 R SW  
BOOK PAGE 40 LINE 18

PAM-KAR DRILLING CO., INC.  
WICHITA, KANSAS

WELL: COBERLY # 1

SW SW NE  
Sec. 25-23-5  
RENO COUNTY

COMMENCED RD 6-18-54  
COMPLETED RD 7-2-54

ELEVATION: 1496 ~~FE~~

CASING: 207' 13" O.D. 8V thd

CONTRACTOR: PAM-KAR

TOTAL DEPTH: 3890

STRATA	DEPTH	TOPS
Sand	12	Base KC 1497
Gravel	165	Marmatom 3146
Clay	175	Cherokee 3293
Shale	182	Cong. 3366
Shale & Clay	223	Mississippi 3376-1879
Shale	284	Osage 3388-1891
Shale & Shells	445	Kinderhook 3592-2095
Salt	650	Misnor-
Shale & Shells	705	Hantom 3734-2237
Shale, Shells & Lime	715	Maguoketa 3776-2279
Lime & Shale	915	Viola 3840-2343
Broken Lime	1085	Simpson 3864-2367
Shale & Shells	1447	
Shale & Lime	1625	D. & A
Lime & Shale	2360	
Broken Lime	2455	
Lime & Shale	2703	
Broken Lime	2800	
Lime & Shale	3300	
Lime, Shale & Chirt	3390	
Lime & Shale	3602	
Shale	3642	
Lime & Shale	3676	
Shale & Lime	3734	
Sand	3740	
Sand & Shale	3771	
Shale & Lime	3792	
Sand, Shale & Lime	3890	
Total Depth	3890	

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1954  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

PAM-KAR DRILLING CO., INC.  
BY

*Ralph B. McLaughlin*  
Ralph B. McLaughlin, Sec-Treas.

Signed and sworn to in my presence this 12th day of July, 1954, by Ralph B. McLaughlin, Secretary-Treasurer of the Pam-Kar Drilling Co., Inc., a corporation in the State of Kansas.

*John [Signature]*  
Notary Public

My commission expires September 4, 1957.

