

Recd 10-3-80


15-155 20702-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Reno County, Sec. 26 Twp. 23 Rge. 5W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NE SW SE
Lease Owner National Oil Company
Lease Name Brawner Prospect Well No. 1
Office Address 200 W. Douglas-Suite 550, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed September 29, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced September 29, 1980
Plugging completed September 29, 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 13,860'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	337'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 3,860 ft. (rotary total depth) to 450 ft. Set plug at 450 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 450 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Employer of owner)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water #10 Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1980

Elsie Willison - Notary Public.

My commission expires July 25, 1982



KANSAS DRILLERS LOG

COMPANY National Oil Company

SEC. 26 T. 23 R. 5W
LOC. NE SW SE

FARM Brawner Prospect No. 1

COUNTY Reno

ROTARY TOTAL DEPTH 3,860'

COMM. September 21, 1980 COMP. September 29, 1980

CONTRACTOR H-30, INC. (Rig #7)

ISSUED October 9, 1980

CASING

10 3/4"

8 5/8" Set at 337' cemented w/275 sxs cement

ELEVATION 1,500' K.E.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	338'
Shale	672'
Lime and Shale	3,860'
Rotary Total Depth	3,860'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas)
) SS:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 9th day of October, 1980.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982