

15-155-02049-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Reno County. Sec. 35 Twp. 23 Rge. 5 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NE NE SE
Lease Owner Pam-Kar Drilling Company
Lease Name Bacon B Well No. 1
Office Address 333 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 15 19 54
Application for plugging filed August 15 19 54
Application for plugging approved August 15 19 54
Plugging commenced August 15 19 54
Plugging completed August 15 19 54
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	141	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pits were gunned and very heavy mud circulated. Hole was circulated 1 1/2 hrs. Pushed plug to 136'. Poured 1/2 sack hulls on top of plug. Poured 25 sks of cement, filling hole to 20', pushed plug to 20' poured 1/2 sk of hulls and 8 sks cement filling hole. All plugs were secured with 2 strands of .066 steel line.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pam-Kar Drilling Company, Inc.
Address 333 First National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B. McLaughlin

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 54

(Address)

[Signature]

Notary Public.

My commission expires September 4, 1957

PLUGGING
FILE SEC. 35 TWP. 23 R. 5W
BOOK 56 PAGE 45

RECEIVED
STATE CORPORATION COMMISSION
8-24-54
CONSERVATION DIVISION

15-155-02049-0000

PAM-KAR DRILLING CO., INC.

WICHITA, KANSAS

WELL: BACON B

NE NE SE

COMMENCED RD 8-6-54

35-23-5

COMPLETED RD 8-15-54

RENO COUNTY

DEPTH: 3430

ELEVATION: 1496 DF

CASING: 141' 13 3/8 O.D.

CONTRACTOR: PAM-KAR DRLG. CO. INC.

STRATA	DEPTH	TOPS
Surface, soil, sand & gravel	115	Conglomerate 3371-1875
Shale	145	Warsaw 3373-1877
Shale & shells	285	Osage 3383-1887
Shale	424	
Salt	618	D & A
Broken Lime	690	
Shale & Lime	1350	
Lime & shale	2840	
Lime, shale & chirt	3410	
Chat	3430	
Lime, chirt & shale	3430	
Total Depth	3430	

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

PAM-KAR DRILLING CO., INC.
BY

Ralph B. McLaughlin
Ralph B. McLaughlin Sec. Treas.

Signed and sworn to in my presence this 23rd day of August, 1954, by Ralph B. McLaughlin, Secretary-Treasurer of the Pam-Kar Drilling Co., Inc. a corporation in the state of Kansas.

Arnold Wiley
Notary Public

My commission expires September 4, 1957.

PLUGGING
WELL SEC 35 23 SW
BOOK PAGE 56 LINE 45

RECEIVED
CORPORATION COMMISSION
AUG 23 1954
REGISTRATION DIVISION
Wichita, Kansas