

STATE OF KANSAS  
 STATE CONSERVATION COMMISSION  
 30 Colorado Dorby Building  
 Wichita, Kansas 67202

**WELL PLUGGING RECORD**  
 K.A.R.-02-3-117

API NUMBER 15-155-21048-0000

LEASE NAME Bacon

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

330 Ft. from S Section Line

4620 Ft. from E Section Line

4950  
 feet  
 14-1

SEC. 35 TWP. 23S RGE. 5W (E) or (W)

LEASE OPERATOR KTA/Gressel Operating

COUNTY Reno

ADDRESS Box 327 Haysville, Ks. 67060

Date Well Completed 5-15-85

PHONE# ( ) 773-1247 OPERATORS LICENSE NO. 3626

Plugging Commenced 7-1-88

Character of Well oil

Plugging Completed 7-2-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Wichita, Ks.

ACO-1 filed? yes If not, is well log attached? N/A

Producing Formation Simpson Depth to Top 3846 Bottom 3854 T.D. 3854

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

Formation	Content	From	To	Size	Put In	Pulled out
Surface	water	0	635	8 5/8	635	None
Simpson	water	0	3846	5 1/2	3846	2520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sand back to 3750', spot 6 sacks cement, rip pipe at 2520', mud to 700', build rock bridge, Redimix to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corp. License No. 5822

Address Haysville, Ks. 67060

STATE OF Kansas COUNTY OF Sedgwick, ss.

Kevin T. Allam

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kevin T. Allam

(Address) Wichita, Ks.

STATE CONSERVATION COMMISSION  
 7-5-88  
 5 1988

SUBSCRIBED AND SWORN TO before me this 5 day of July, 19 88  
 CONSERVATION DIVISION  
 Wichita, Kansas

My Commission Expires



Gary D. Stearns  
 Notary Public

PATE-DOMBAUGH PETROLEUM & MARTIN OPERATIONS  
#1 BACON SW SW SW  
SECTION 35, T23S-R5W  
RENO COUNTY, KANSAS

*Dist ACO  
8/24/85  
letter of confidentiality*

15-155-21098-0000

GEOLOGIST: RAYMOND R. DOMBAUGH

STARTED: 4/25/85

COMPLETED:

DRILLED BY: KAW DRILLING CO., INC.

ELEVATION: 1498 G.L.  
1509 K.B.

DAILY REPORT

4/25/85 SPUD 4:45 P.M. DRILLED 650'- 12 $\frac{1}{4}$ " HOLE.  
RAN 15 JTS. 8 5/8" CASING. TALLIED 635'.  
SET AT 647 K.B. W/300 SX. 1 GHT, 150 SX.  
COM., 3% CC, 2% GEL. PLUG DOWN AT 7:45  
A.M. 4-26-85.

4/29/85 DRILLING AT 2790'.

4/30/85 DRILLING AT 3248'.

5/01/85 DRILLING AT 3634'.  
DST #1 (3844'-3856')  
OP. 30; CL. 45, OP. 60, CL. 60  
STRONG BLOW  
RECOVERED 840' GAS IN PIPE  
1,400' OIL, 38°  
120' MUDDY OIL  
795' WATER

IBHP 1129'/45"  
IF 170#-477# FF 612#-531#  
FBHP 1129#/60"

5/02/85 PREPARING TO RUN LOG.  
T.D. 3856'. Ran 95 jts. of  
5 $\frac{1}{2}$ " casing. Tallied 3858'.  
Set at 3846' with 100 sacks  
of 60/40 pozmix, 3% c.c., 2% gel;  
10 bbl. salt flush and 3/4% CFR2.  
Plug down at 11:20 p.m.

TOPS

HEEBNER	2510(-1001)
LANSING	2692(-1183)
B/KC	3136(-1627)
CHEROKEE	3291(-1782)
MISS.	3396(-1887)
M. CHERT	3422(-1913)
KINDERHOOK	3616(-2107)
HUNTON	3749(-2240)
VIOLA	3841(-2332)
TD	3856(-2347)

Electric Log Tops

Heebner	2505(- 996)
Lansing	2690(-1181)
B/KC	3131(-1622)
Miss.	3384(-1875)
Kinderhook	3609(-2100)
Hunton	3747(-2238)
Viola	3835(-2326)
Simpson	3846(-2337)
TD	3854(-2345)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1988

CONSERVATION DIVISION  
Wichita, Kansas