

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1965
5-21-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma

Lease Name Howell "B" Well No. # 1

Location SW SW NE Sec. 31 Twp. 29 Rge. 14 (E) (W) W

County Pratt Total Depth 4620'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Graybol Oil Corporation

Address: 2200 National Bank of Tulsa, Tulsa, Oklahoma License No. _____

Operation Completed: Hour 4:30 AM Day 20th Month May Year 1965

The Above well was plugged as follows:

323' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged
solid with hulls on fluid at 300', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged sol-
id with hulls on fluid at 40', and cemented with 10 sacks to the base
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/21/65

INV. NO. 1196-W