

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Rec'd
10-19-64

Operator's Full Name Graybol
Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Building, Tulsa, OKLAHOMA

Lease Name Howell Well No. #2

Location C-SW-SE Sec. 31 Twp. 29 Rge. 14 (E) (W) W

County Pratt Total Depth 4661

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Incorporated

Address: Box 221 Great Bend, KANSAS License No. 49

Operation Completed: Hour 5:30 PM Day 15 Month 10 Year 1964

The Above well was plugged as follows:

322 feet of 8 5/8 inch surface pipe cemented with 230 sacks cement. 4600 feet of
4 1/2 inch long string cemented with 150 sacks. Plug back to 4561 top perforated
4544 feet sand to 4520 cemented with 3 sacks. Mud to 250 feet. 10 feet Rock Bridge
cemented with 25 sacks mud to 40 feet; 10 feet Rock Bridge cemented with 10 sacks
cement to base of cellar. 2420 feet of 4 1/2 inch pipe pulled.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/19/64
INV. NO. 12-W

Signed: Kerman J. Justus
Well Plugging Supervisor