

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

*R*

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Pratt

Location: NE NE SW Sec. 7 Twp. 26 Rge. 13 (E) (W) X

Name of Field: \_\_\_\_\_ Total Depth: 4910

I have this date completed supervision of plugging of:

Lease Name: Toland "B" Well No. 1

Operator's Full Name: Twon Drilling Co.

Complete Address: 1005 Central Bldg, Wichita, Kans.

Plugging Contractor: West Supply

Address: Chase, Kans. License No. \_\_\_\_\_

Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4PM Day 22 Month Aug. Year 1958

The above well was plugged as follows:

220' of 13 3/8" surface casing circulated with cement. Top perf. 3929'.  
Sanded hole to 3929' and dumped five sack cement with dump bailer. Shot  
off pipe at 2024'. Pulled pipe to 800' and circulated rotary mud from  
pit. Heavy mud to 220'. Set rock bridge at 220' to 210' and dumped 20  
sack cement top bridge. Heavy mud to 35'. Rock bridge to 25'. Cement  
to base of cellar.

Signed: *W. H. Kemp*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC 7 T 26 R 13W  
BOOK PAGE 127 LINE 8

REC'D  
AUG 29 1958  
8-29-58  
CONSERVATION DIVISION  
WICHITA, KANSAS