

1 120879

1-24

To: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PLUGGING SECTION 200 COLORADO DERBY BUILDING WICHITA, KANSAS 67202

API NUMBER 15- 185-21,909-0000
N2 N2
NE NE SW, SEC. 23, T 24 S, R 11 W/8
2310 feet from S section line
3960
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Lease Name C. Paulsen Well # 1

Operator: RAMA Operating Company, Inc.

County Stafford 129.94

Name & Address P.O. Box 159

Well Total Depth 3998 feet

Stafford, KS 67578

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:15 p.m. Day: 24 Months: 1 Year: 19 94

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

vers: 5 1/2" at 3998' w/125 sx cement,

- 1st plug sand back to 3750' and dump 5 sx cement on top of sand through bailer,
- 2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
- 8 5/8" wiper plug and pump 125 sx cement.

RECEIVED 2-1-94
STATE CORPORATION COMMISSION
Glenn Barlow
PLUGGING - 1 1994 (TECHNICIAN)

Plugging Proposal Received

Plugging Operations attended by Agent?: All None _____

Operations Completed: Hour: 4:45 p.m. Day: 24 Month: 1 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3750' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (Back) observe this plugging.

DATE 2-4-94

Signed Glenn Barlow (TECHNICIAN)

INV. NO. 39872