

To: 1 120880
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-24

API NUMBER 15-185-22,002-0000
N/2 NW SW, SEC. 23, T. 24 S, R. 11 W/E
2310 feet from S section line
660 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911
Operator: RAMA Operating Company, Inc.
Name & Address P.O. Box 159
Stafford, KS 67578

Lease Name C. Paulsen Well # 2
County Stafford
Well Total Depth 4230 137.48 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 24 Month: 1 Year: 19 94

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

was: 4 1/2" at 4180' w/175 sx cement, Perfs at 3811-17'

1st plug sand back to 3750' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

2-1-94

RECEIVED
STATE CORPORATION COMMISSION

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)
FEB 1 1994

Plugging Operations attended by Agent?: All CONSERVATION DIVISION Part Division _____ None _____
Wichita, Kansas

Operations Completed: Hour: 3:10 p.m. Day: 24 Month: 1 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3750' and dumped 4 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if additional description is necessary, use BACK of this form.)
observe this plugging.

DATE 2-4-94

Signed D. J. Rink (TECHNICIAN)

INV. NO. 39873