

12-21-87 15-185-11307-0000
Docket #E-18,099

1040030

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 7805

Operator: King & Rowe Oil Company

Name & Address 118 West Chestnut

Stafford, KS 67578

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 21 Month: 12 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5½" at 3888' Perfs at 3818-64' PBTD 3364'

1st plug sand back to 50' above PBTD and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls and 150 sx Econolight.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1 p.m. Day: 21 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3300' with 5 sx cement on top of sand
through dump bailer.

2nd plug pumped down 8 5/8" with 200 lbs. hulls ahead of cement and 200 lbs. hulls in with
first part of cement and 150 sx cement. Maximum pressure 100 psi and shut in 0 psi.
Well on vacuum.

Remarks: Used ATL cement by Allied. Recovered 830' of 5½" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 1-6-88

INV. NO. 19379

Signed Stephen J. Pfeifer
(TECHNICIAN)