

1 120892

2-18

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-22,510-0000

NE SE NE, SEC. 22, 7 24 S, R 11 W/X

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408

Lease Name Richardson Well # 1

Operator: Trans Pacific Oil Corporation

County Stafford

Name & Address One Main Place, Ste. 1000

Well Total Depth 3840 124.80 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 18 Month: 2 Year: 19 94

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 5 1/2" at 3833' w/90 sx cement, Open hole completion

1st plug sand back to 3790' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 18 Month: 2 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back 5 1/2" casing to 3775' and dumped 5 sx cement on top of sand through bailer,

RECEIVED  
STATE CORPORATION COMMISSION

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

FEB 24 1994

CONSERVATION DIVISION  
Wichita, Kansas

2-24-94

Pumping pressure 0-500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed *Darrell Kelso*  
(TECHNICIAN)

DATE FEB 25 1994

INV. NO. 40045