

1052355

TO:
STATE CORPORATION COMMISSIONAPI NUMBER 15-185-22,184-0000
NE SE NE SEC. 21, T 24 S, R 11 WCONSERVATION DIVISION - PLUGGING SECTION 3620 FEET FROM SOUTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BAUER WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 132.44OPERATOR LICENSE # 5506WELL TOTAL DEPTH 4075 FEETOPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4074' WITH 175 SXNAME AND PO BOX 168 SURFACE CASING: SIZE 8 5/8" @ 257' WITH SXADDRESS MEDICINE LODGE, KS 67104ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR PRATT WELL SERVICE LICENSE NUMBER 5893ADDRESS PO BOX 847 PRATT, KS 67124COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 01 MONTH: 12 YEAR: 1999PLUGGING PROPOSAL RECEIVED FROM ALLEN DICK(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531

WERE: PERFS AT 3886-88, 3828-30, 3819-21

SANDED TO 3750' AND 5 SX CEMENT. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT

10 SX GEL - 100# HULLS - 8 5/8" PLUG - 125 SX CEMENT. MAXIMUM PRESSURE AT 400#. SHUT IN

WITH 250#.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEYPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE OPERATIONS COMPLETED: HOUR: 12:20 PM DAY: 01 MONTH: 12 YEAR: 1999ACTUAL PLUGGING REPORT

SANDED TO 3750' AND 5 SX CEMENT. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX

CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" PLUG - 125 SX CEMENT. MAXIMUM PRESSURE AT 400#.

SHUT IN WITH 250#.

DEC 02 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1723' OF 5 1/2" CASING WITH DIVISION

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

DATE 12/23/99

SIGNED

Richard M. Lacey
(TECHNICIAN)

FORM CP-213

INV. NO. 061037