

6-15-88

00875

API NUMBER 15-185-01,031 - 0001

To: 1 120104
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SW, SEC. 19, T 24 S, R 11 (W) 1/4

2310 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408

Lease Name V & E, Inc. Well # 1

Operator: Trans Pacific Oil Corporation
Name & Address 410 One Main Place

County Stafford 134.00

Well Total Depth 4123 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling License Number 7182

Address Route 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 15 Month: 6 Year: 19 88

Plugging proposal received from L.D. Davis

(company name) L.D. Drilling (phone) 316-793-3051

were: 4 1/2" at 4121' PBSD 3500' Perf top 3500'

1st plug sand back to 3450' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1 p.m. Day: 15 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3450' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1800' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-30-88

INV. NO. 21151

Signed Duane Rankin (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1988
6-21-88
CONSERVATION DIVISION
Wichita, Kansas