

1020167

API NUMBER 15-185-22,122 - 6600

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C E/2 NE NE, SEC. 16, T 24 S, R 11 W/E

4620 feet from ~~XX~~/S section line
330 feet from ~~XX~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482

Lease Name Meyer Well # 1

Operator: National Petroleum Reserves, Inc.
Name & Address 260 North Rock Road, Suite 215
Wichita, KS 67206

County Stafford 126.10

Well Total Depth 3880 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling Co., Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 1 Month: December Year: 19 84

Plugging proposal received from Victor Gustus

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 720' with 50 sx cement

2nd plug at 350' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plug water well with 5 sx cement

Plugging Proposal Received by [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:30 pm Day: 1 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 720' with 50 sx cement, 2nd plug at 350' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, and plugged water

well with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
12-5-84
DEC 05 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this CONSERVATION DIVISION
Wichita, Kansas

NOTICED

(If not) observe this plugging.

DATE 12-20-84

Signed [Signature]
(TECHNICIAN)

INV. NO. 6076