

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21961-00-00  
Spot: CS2S2NE Sec/Twnshp/Rge: 23-24S-11W  
2970 feet from S Section Line, 1320 feet from E Section Line  
Lease/Unit Name: ZENITH UNIT Well Number: 16  
County: STAFFORD Total Vertical Depth: 3901 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 261  
Production: Size 5.5 feet: 3885  
Liner: Size feet:

\$126.78

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/02/2001 1:45 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3450' & 5 SX CMT. 1ST PLUG AT 600' WITH 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/02/2001 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 3540-3800'. SANDED BACK TO 3450' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 600' WITH 8 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2334' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED

NOV 09 2001

KCC WICHITA

Signed

Stephen J. Pfeifer  
(TECHNICIAN)

INVOICEL

NOV 05 2001

DATE

11-9-01

INV. NO.

2002060928

Form CH 23