

1 070036

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,725 - 00-00

C SE SE SW, SEC. 3, T 29 S, R 15 W/A

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Whitney Well # 1

Operator: VAC Petroleum Company

County Pratt 154.99

Name & Address 333 North Rock Road, Suite 105

Well Total Depth 4769 Simpson feet

Wichita, KS 67206

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Company License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 1:00 am Day: 25 Month: October Year: 19 85

Plugging proposal received from Wayne Boughner

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe Elevation N/A
Anhydrite 920-950'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 3:00 am Day: 25 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 950' with 50 sx cement, 2nd plug at 460' with 50 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rathole with 10 sx cement, 6th plug to

circulate mouse hole with 10 sx cement

RECEIVED

STATE CORPORATION COMMISSION

10-28-85

OCT 28 1985

Remarks: used 60/40 Pozmix 6% gel by Halliburton CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

I () did not observe this plugging.

DATE OCT 29 1985

Signed Dan Goodrow
(TECHNICIAN) *D.G.*

INV. NO. 10813