

To: 1 041150
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 151-21,624 - 00-00
SE SE SE, SEC. 5, T 29 S, R 15 W/E
330 feet from S section line
330 feet from E section line

2-22

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893

Lease Name Carver Well # 1

Operator: Pratt Well Service Inc.

County Pratt

Name & Address P.O. Box 847

Well Total Depth 4747 154.28 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 396

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:45 a.m. Day: 22 Month: 2 Year: 1996

Plugging proposal received from Kenny Gates

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4746' w/150 sx cement, PBTD 4600', Perfs at 4740-42, 4464-68'

1st plug sand back to 4410' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

2-29-96

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 a.m. Day: 22 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4410' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3423' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (and all) observe this plugging.

Signed *Steve Pfeifer*
(TECHNICIAN)

INVOICED

DATE MAR 05 1996

INV. NO. 44950