

030527

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,644 -00-00 *R*

SE SE SE, SEC. 7, T 29 S, R 15 (W)EX

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name House Well # 1

Operator: Raymond Oil Company, Inc.
Name & Address One Main Place, Suite 900
Wichita, KS 67202

County Pratt 159.25

Well Total Depth 4900 Simpson Sand feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 389

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Company, Inc. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 4:00 pm Day: 18 Month: September Year: 19 85

Plugging proposal received from Larry Harris

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe Elevation Est. 2060 Anhydrite 950'

- 1st plug at the base of the Anhydrite with 50 sx cement
- 2nd plug 30' out of the base of the surface pipe with 40 sx cement solid bridge
- 3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 5th plug to circulate rat hole with 10 sx cement
- 6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 pm Day: 18 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 960' with 50 sx cement, 2nd plug at 417' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 23 1985

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan. CONSERVATION DIVISION Wichita, Kansas
(If additional description is necessary, use BACK of this form.)

INVOICED
If you did not observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE SEP 24 1985

INV. NO. 10245