

1 040147

8-18-88

API NUMBER 15- 151-21,557-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW SE, SEC. 4, T 29 S, R 15 W/EX

990 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Maxedon Trust Well # 2

Operator: Raymond Oil Company, Inc.
Name & Address P.O. Box 48788
Wichita, KS 67201

County Pratt 158.28
Well Total Depth 4870 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 5:15 p.m. Day: 18 Month: 8 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4846' PBSD 4786' Top perfs 4446-54' (5 sets)
1st plug sand back to 4550' and dump 5 sx cement on top of sand through bailer,
2ns plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

8-23-88

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:45 p.m. Day: 18 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4390' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 850 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3040' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 8-24-88

NV. NO. 21908