

To: 1 040614
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-31 API NUMBER 15- 151-21,516-60.00 164

SW SE SW, SEC. 4, T. 29 S, R. 15 W
330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399
Operator: Farrar Pump & Supply Co. Inc.
Name & Address: Jct. 160 & 281 NW
Medicine Lodge, KS 67104

Lease Name Spines Well # 2-4
County Pratt 157.95
Well Total Depth 4860 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 4:15 p.m. Day: 31 Month: 1 Year: 19 92

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4859' w/200 sx cement, PBSD 4859', Perfs at 4694-4724'
1st plug sand back to 4645' and dump 5 sx cement on top of sand bridge through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 31 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4645' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 600 psi and shut in 250 psi.

STATE CORPORATION COMMISSION

FEB 04 1992 2-4-92

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3162' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-11-92
34497

Signed Stephen J. Pfeifer
(TECHNICIAN)