

1 040615 1-31  
To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Operator: Farrar Pump & Supply Co. Inc.

Name:

Address Jct. 160 & 281 NW

Medicine Lodge, KS 67104

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 31 Month: 1 Year: 1992

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4849' w/200 sx cement, PBSD 4849', Perfs at 4475-81, 4491-95'

1st plug sand back to 4425' and dump 5 sx cement on top of sand bridge through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer.  
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 2:30 p.m. Day: 31 Month: 1 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 4425' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 800 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2708' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 2-11-92

WELL NO. 34498

API NUMBER 13- 151-21,560 - 00-00 164  
SE SE SW, SEC. 4, T. 29 S, R. 15 W/E

330 feet from S section line

2970 feet from E section line

Lease Name Spines Well # 3-4

County Pratt 157.65

Well Total Depth 4851 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 429

SWD Well D&A

License Number 4635

Year: 1992

(phone) 316-793-9711

(TECHNICIAN)

None

Year: 1992

FEB 04 1992 2-4-92

CONSERVATION DIVISION  
WICHITA, KANSAS

Signed Stephen J. Pfeifer  
(TECHNICIAN)