

1 080464

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,581-60-60
SE SW SE, SEC. 4, T 29 S, R 15 W/EX

330 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Maxedon Trust Well # 3

Operator: Raymond Oil Company, Inc.

County Pratt 144.95

Name & Address One Main Place, Suite 900

Well Total Depth 4460 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 386

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 am Day: 27 Month: December Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4592' PBD 4449' Perfs at 4441-4449'

1st plug pump 30 sx cement and stop plug at 4300'

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:15 pm Day: 27 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement to bottom and stopped plug at 4300'

shut in 900 psi. 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 400 psi

Remarks: Recovered 3451' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE JAN 06 1986

INV. NO. 11850

1-2-86

JAN 2

1985

Signed

J. A. [Signature]
(TECHNICIAN)