

To: 1 040708  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-16 API NUMBER 15-151-20,376-A <sup>-60.61</sup> 105R

C NE NE, SEC. 9, T. 29 S, R. 15 W/E  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5046  
Operator: Raymond Oil Company, Inc.  
Name & Address P.O. Box 48788  
Wichita, KS 67201

Lease Name Bryant Well # 1  
County Pratt 157.72  
Well Total Depth 4853 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 16 Month: 10 Year: 19 92

Plugging proposal received from Monty Andrews  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" Perfs at 4458-68'  
1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 2:30 p.m. Day: 16 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand bridge through bailer.  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement. 10-22-92  
Maximum pressure 600 psi and shut in 250 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by United Cementing. Recovered 3200' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

1 (if observed) observe this plugging.

INVOICED  
DATE 10-29-92  
INV. NO. 36630

Signed Stephen J. Pfeifer  
(TECHNICIAN)