

To: 1 120682  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2-18 API NUMBER 15 151-21,566-00-00 136  
NW NW NE, SEC. 9, T. 29 S, R. 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5303  
Operator: Canaday Oil Corporation  
Name &  
Address 920 N. Tyler, Suite 104  
Wichita, KS 67212

4950 feet from S section line  
2310 feet from E section line  
Lease Name Bryant Well # C-1  
County Pratt 156.32  
Well Total Depth 4810 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 373

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 18 Month: 2 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

work: 4 1/2" at 4809' w/200 sx cement, PBD 4800', Perfs at 4454-66'  
1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 18 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4400' and dumped 4 sx cement on  
top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement. 2-26-92  
Pumping pressure 0-500 psi and shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 4 1/2" casing. FEB 26 1992  
(if additional description is necessary, use BACK of this form.)

**INVOICED** Observe this plugging.

Signed Dean Rankin  
(TECHNICIAN)

DATE 2-2-92  
INV. NO. 34666