

To: 1 040710  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-16 API NUMBER 15- 151-21,491 -00.00 102  
NW NE NW, SEC. 9, T. 29 S, R. 15 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046  
Operator: Raymond Oil Company, Inc.  
Name & Address: P.O. Box 48788  
Wichita, KS 67201

4950 feet from S section line  
3630 feet from E section line  
Lease Name Bryant Well # 2  
County Pratt 156.75  
Well Total Depth 4823 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 16 Month: 10 Year: 19 92

Plugging proposal received from Monty Andrews  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4822' w/200 sx cement, PBD 4747', Perfs at 4491-98'  
1st plug sand back to 4440' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125. sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None   
Operations Completed: Hour: 11 a.m. Day: 16 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4440' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 1000 psi and shut in 900 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by United Cementing. Recovered 3200' of 4 1/2" casing. 2 1992  
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 10-29-92  
V. NO. 36627

Signed Stephen J. Pfeifer  
(TECHNICIAN)