

To: 1 040709  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-16

API NUMBER 15- 151-21,574 - 40-00 104  
NW NW NW, SEC. 9, T. 29 S, R 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Operator: Raymond Oil Company, Inc.  
Name & Address  
P.O. Box 48788  
Wichita, KS 67201

4950 feet from S section line  
4950 feet from E section line

Lease Name Bryant Well # 3 C  
County Pratt 156.00

Well Total Depth 4800 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 16 Month: 10 Year: 19 92

Plugging proposal received from Monty Andrews

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4797' w/175 sx cement, PBD 4770', Perfs at 4463-68'  
1st plug sand back to 4410' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 16 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4410' and dumped 5 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by United Cementing. Recovered 2500' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOLVED  
I did not observe this plugging.

DATE 10-29-92  
INV. NO. 36629

Signed Stephen J. Pfeifer  
(TECHNICIAN)