

To: 120683 2-18  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,565-00-00 138p  
NE NW NW, SEC. 9, T. 29 S, R. 15 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5303  
Operator: Canaday Oil Corporation  
Name & Address 920 N. Tyler, Suite 104  
Wichita, KS 67212

4950 feet from S section line  
4290 feet from E section line  
Lease Name Bryant Well # 2  
County Pratt 156.03  
Well Total Depth 4801 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 356

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 18 Month: 2 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4799' w/175 sx cement, Perfs at 4632-40' & 4679-84'

1st plug pump 2 sx hulls and 30 sx common cement to 3500',

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 18 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped in 5 1/2" casing with 200 lbs. hulls and 30 sx  
common cement, pushed plug to 3500',

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

I (Signature) observe this plugging.

DATE 3-3-92

INV. NO. 34668

Signed (Signature)  
(TECHNICIAN)

2-26-92 RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

FEB 26 1992

CONSERVATION DIVISION  
WICHITA, KANSAS