

1 040944 3-31

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-24,273

NW SW NW, SEC. 9, T 29 S, R 15 W/E
3630 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767

Lease Name Bryant C-P Well # 4
County Pratt 156.13

Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market, Ste. 1000
Wichita, KS 67202

Well Total Depth 4804 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at Hour: 3:45 p.m. Day: 31 Month: 3 Year: 1995

Plugging proposal received from Bennie Dill

(company name) Ritchie Exploration (phone) 316-793-2525

were: 4 1/2" at 4805' w/125 sx cement, PBTD 4791'; Perfs at 4704-30'
1st plug sand back to 4630' and dump 5 sx cement on top of sand through bailer;
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:30 p.m. Day: 31 Month: 3 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4630' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 200 lbs. hulls and 100 sx cement. Maximum pressure 600 psi and shut in 350 psi.

Plugged fresh water supply well with 15 sx cement.

(No wiper plug. Surface pipe plated with 5 1/2" collar.)

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (X) Observe this plugging.

DATE 4-10-95

INV. NO. 42552

Signed Steve Pfeifer (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR - 6 1995
WICHITA, KANSAS