

To: 1 010094
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,770 - 00-00
SW NE SW 1, SEC. 10, T 29 S, R 15 W EX
1650 feet from S section line
3630 feet from E section line
Lease Name Hogard Well # 1-A
County Pratt 157.63
Well Total Depth 4850 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 345

TECHNICIAN'S PLUGGING REPORT
Operator License # 5046
Operator: Raymond Oil Company, Inc.
Name & Address P. O. Box 48788
Wichita, KS 67201

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P. O. Box 18611, Wichita, KS 67218

Company to plug at: Hour: 3:00 pm Day: 24 Month: February Year: 19 86

Plugging proposal received from Mark Guinn

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1260
Elevation 1970

- 1st plug at the base of the Anhydrite with 50 sx cement
- 2nd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge
- 3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 5th plug to circulate rat hole with 15 sx cement
- 6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Jack L. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 pm Day: 24 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1280' with 50 sx cement, 2nd plug at 379' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

3-4-86

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(if additional description is necessary, use BACK of this form)

MAR 4 1986

INVOICED
MAR 04 1986
DATE _____
INV. NO. 12865

Signed Jack L. Luthi
(TECHNICIAN)

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas